



CPTSB ITEMS TO BE COMPLETED PRIOR TO OPENING

During the licensing annual inspection, all of the following items may or may not be in place for the Inspector to observe. For winter operation, it is understood that with early season snow conditions, snow may be nonexistent and that you remove many of these items because of vandalism, construction etc., when the lift is not being operated for public operation.

IT IS THE RESPONSIBILITY OF THE OPERATOR TO HAVE ALL OF THESE ITEMS IN PLACE PRIOR TO OPERATION OF THE LIFT FOR PUBLIC USE.

- X.1.1.5.1 Vertical clearances. Install appropriate barriers where there is inadequate clearance under the lift line.
- X.1.1.5.1 Vertical clearances. Remove temporary closure barriers that do not have adequate clearance under the lift.
- X.1.1.9 Loading and unloading areas. Properly prepare the surface at loading and unloading areas.
- X.1.2.6 Brakes and rollback devices. Torque test all brakes according to the approved torque test procedures.
- X.1.2.10.2 Counterweights. Install appropriate fencing around counterweights to prevent unauthorized persons from coming in contact with or passing under counterweight.
- X.1.5 Provisions for operating personnel. Supply operating instructions and emergency procedures in all operators and attendants stations.
- X.2.3.2 Stop Gates. Where appropriate, properly install all removable stop gate wands or ropes.
- Annex F.7 Provisions for operating personnel. Provide properly certified fire extinguishers that are correctly hung in all operator and attendants stations and in the machine room.
- X.2.13.4 Emergency lighting. For those lifts that operate at night, verify that the emergency lighting is properly installed and is functional.
- X.3.1.2 Signs. Post all required signs at loading and unloading areas.
- X.3.2.1.5 First aid. Provide all required first aid equipment, personnel, and supplies prior to public operation.
- X.3.2.4.1 Control of passengers. Install appropriate fencing and gates at the loading area for the marshaling of passengers.
- X.3.3 General (Maintenance). Complete all tramway maintenance that is defined on the maintenance schedule as required prior to public operations.

If these items are not completed upon opening to public operation, they may be considered a PREVIOUS DEFICIENCY during the Unannounced Inspection.